

Estimate

CON-SULT MECHANICAL INC
54 AUDIA CRT, UNIT #2
CONCORD, ON L4K 3N4

Date	Estimate #
2025-02-11	1082

Name / Address

TOWN SQUARE DEVELOPMENTS
152 KILORAN AVE
WOODBIDGE, ON L4L 3M3
PROJECT: 227 PARK HOME, NORTH YORK

Project

227 PARK HOME, NORTH YORK

Description	Qty	Cost	Total
S & I TWO (2) YORK 2 STAGE VARIABLE SPEED GAS FURNACE S & I SHEET METAL DISTRIBUTION SYSTEM FOR HVAC SYSTEMS C/W MEDIA AIR CLEANERS. ALL DUCTING TO BE INSTALLED AS PER LOCAL CODES AS WELL AS MANUFACTURERS INSTRUCTIONS. ALL DUCTING TO BE SEALED WITH HIGH VELOCITY DUCT SEALANT. 2 HONEYWELL WIFI THERMOSTATS S & I MAIN GAS LINE FROM METER LOCATION OUTSIDE TO INSIDE MAIN MECHANICAL ROOM TO MAIN GAS MANIFOLD TO GAS AND VENT 2 GAS FURNACES. TO INSTALL GAS MANIFOLD WITH CAPPED VALVES FOR BOILER AND FIREPLACES S & I TWO (2) YORK AIR CONDITIONERS C/W REFRIGERANT LINES, AND LOW VOLTAGE WIRING. ALL LINES TO BE PRESSURE TESTED, EVACUATED AND CHARGES FOR LINESET COMPENSATION. UPGRADE TO 2 YORK HMM SERIES HEAT PUMPS PROJECT CLOSE OUT BINDER AND AIR BALANCING WITH REPORT		49,750.00	49,750.00
S & I 2 ERV SYSTEM DUCTED AS SIMPLIFIED SYSTEMS VANE90	2	1,063.00	2,126.00
S & I 1 APRILAIRE STEAM HUMIDIFIER - COST PER - OPTIONAL	2	2,200.00	4,400.00
FLOW THROUGH HUMIDIFIER	0	1,800.00	0.00
	2	650.00	1,300.00
Sales Tax Summary		Subtotal	
		Sales Tax Total	
		Total	

GST/HST No. 832560288

Customer Signature