



54 Audia Court, Unit 2
Concord, ON L4K 3N5
(905)-738-1400

Change Order Quote

Project: 2299 DUNDAS - SHELTER RENOVATION

Date: Feb 13, 2025

Change Order No.: 24-229-COR012

Attn

Issued by

Paddy Devlin

INZAMAN KHAN

ROSSCLAIR CONTRACTORS INC.

59 COMSTOCK ROAD, UNIT 1 TORONTO, ON M1L 2G6

Quote Validity: 30 Days

Subject: NOPC 21 - Sanitary Relocation

Extra for revised routing of the drainage pipes to the outgoing sanitary main, including manual excavation and backfilling as per NOPC 21.

Note: Tax not included in the price. HST will be extra.

Description	Qty	Unit	Unit Rate	Amount
Labour: 2 people 3 days @8 hrs	48.00	Hrs	125.00	\$6,000.00
Material (refer attached for breakdown)	1.00	Each	1,043.69	\$1,043.69
Administration/Project Management/Procurement/Supervision	1.00	Each	2,500.00	\$2,500.00
			OH & P	\$1,431.55
			Total	\$10,975.24

NOPC 21 Material Breakdown		
Description	Qty (EA)	Amount
6"X10' PVC SDR35 SEWER PIPE CSA B/E GREEN BDS	1	\$ 104.02
4"X10' PVC GREEN SDR35 SEWER PIPE 003645	1	\$ 35.28
6"X45D PVC WYE SDR35 BDS HXHXXH	2	\$ 131.71
6"X4"X45D PVC WYE SDR35 BDS 040307	3	\$ 179.59
6"X45D PVC ELBOW 040506	2	\$ 75.26
6"X90D PVC SHORT TURN ELBOW 040206	2	\$ 97.85
6"X4"PVC RED. CPLG SDR35 BDS 040661	2	\$ 64.97
4"X3"PVC RED. CPLG SDR35 BDS 040654	1	\$ 10.82
4"X45D PVC ELBOW HXH SDR35 BDS	1	\$ 11.09
3"X2"X45D PVC DWV WYE 026196	1	\$ 24.51
B4-4 EPOXY COATED BODY	2	\$ 63.00
R-1 NB CO TOP ASSEMBLY	2	\$ 175.84
950ML PVC S40 SOLVENT CEMENT GREYW/DAUBER	1	\$ 39.69
950ML PRIMER PURPLE PVC/CPVC	1	\$ 30.04
Total		\$ 1,043.69