



54 Audia Court, Unit 2
Concord, ON L4K 3N5
(905)-738-1400

Change Order Quote

Project: Pod Inn Hotel-400 University -Mezzanine Reno

Date: Jan 27, 2025

Change Order No.: 25-000-COR001

Attn

Issued by

WALID ELSAYED

MOHAMMED LODHI

Walid Elsayed - Pod-Inn Hotel Ltd.

289 Hollymount Dr. Mississauga, ON L5R 3X5

Quote Validity: 7 Days

Subject: DAIKIN VRF SYSTEM

Supply of Daikin VRF system (2-3 Weeks Delivery Time compared to MITS 5-6 weeks)
FC-1, 2, 3, 4 DAIKIN COMMERCIAL: 4.0-Ton MSP Concealed Ducted Unit 4 Each Basis of Design
Daikin VRV fan coil units provided for 208-230/1/60 service with the following:

FC-1, 2, 3, 4

Rear Return Slim Ducted Fan Coil Units (FXSQ-TAVJU)

- Unit mounted condensate lift pump (no field installation required)
- Anti-microbial coated drainpan
- Wall mounted controller and/or sensors as required
- ECM blower motor (3-speed)
- Side and bottom access filter rack housing and filter media ships loose for field installation

ITEMS INCLUDED:

- Centralized controller (w/o BACnet)
- Programmable wired remote controllers for indoor units
- Aux. heat integration

Condensing Unit Support Stands

- Outdoor unit support stands for 18" elevation
- Stands ship loose for onsite assembly
- Startup of Daikin VRV system

CU-1, 2 DAIKIN COMMERCIAL: 8 ton, 230V, VRV EMERION HP 2 0 tons Basis of Design

Daikin HEAT PUMP SYSTEM - SPECIFIED SYSTEM IS HEAT RECOVERY

Daikin VRV condensing units provided with the following:

- R-410a refrigerant factory charge in condensing units (remaining charge to be field installed)
- RefNet "Y" refrigerant pipe manifolds factory supplied for field installation
- 10 year parts and 10 year compressor warranty
- 2-wire communications protocol (daisy chain of wiring not included in base price)
- Factory Authorized Startup Services

Note:

Amount quote is only for supplying above mentioned units.

Amount quoted does not include Tax. HST will be extra.

| Description | Qty | Unit | Unit Rate | Amount |
|-----------------|------|------|--------------|--------------------|
| ADDITIONAL COST | 1.00 | Each | 13,600.00 | \$13,600.00 |
| | | | OH & P | \$1,360.00 |
| | | | Total | \$14,960.00 |