

# **Change Order Quote**

Project: SCARBOROUGH WARMING CENTRE PH2 Date: Jan 9, 2025

Change Order No.: 24-247-COR003

Attn Issued by

Taranjeet Singh MOHAMMED LODHI

1568796 ONTARIO INC. C/A RENOKREW
43 LEPAGE COURT TORONTO, ON M3J 1Z9

Quote Validity: 30 Days

# Subject: Main Floor Heat Issue -CLIENT CANCELLED

## Scope of work:

- Drain heating system completely
- Cut pipe branches in 2 locations
- Remove old ceased valve on west radiator
- Install 2 throttle valves
- Refill heating system and bleed

Add in thermostatic control for rads serving shower and washroom,

- remove section of rad , separate piping
- Install and run new supply and return piping into ceiling below (men's washroom)
- Install new branches off 3" headers
- Run thermostat wires and install thermostat.

#### Needed:

Asbestos insulation removed

Entire men's bathroom ceiling removed

- 2 2" cores holes
- 1 (power)120v receptical

### Material:

- 2 1 1/4" threaded gate valves
- 4 pro press black iron couplings
- 2 1 1/4" unions threaded
- 4 1 1/4" threaded 90s
- 6 assorted 1 1/4" threaded black nipples
- 4 1 1/2" ball valves
- 50' 1 1/2" black iron pipe
- 10 1 1/2" hangers swivel
- 12 1 1/2" black iron 90s
- 6 1 1/2" 45s black iron
- 6 1 1/2" couplings
- 2 3" x 1 1/2" pro press black iron tees
- 4 3" pro press black iron couplings
- 1 2 way Bellimo thermostatic control valve 24v
- 1 thermostat with lockable cover

Description	Qty	Unit	Unit Rate	Amount
Labour 2 guys 1 day @ 9hrs	18.00	Hrs	130.00	\$2,340.00
Material	1.00	Each	2,890.88	\$2,890.88
			OH & P	\$784.63
			Total	\$6,015.51